CIVIL/SITE CONSTRUCTION PLANS PRELIMINARY AND FINAL PUD SITE PLAN MISSOURI RIVER BLUFF CONDOMINIUMS 1414 WEST MAIN STREET JEFFERSON CITY, MO ZONED PUD

AUGUST 2005

UTILITY COMPANIES

Water:
Missouri—American Water Company
906 West High Street
Jefferson City, MO 65101
Contact: Kevin Eveler 573—635—6111


Electric: Ameren UE Engineering Department Jefferson City, MO Contact: 573—681—7522

lelephone:
Sprint
3546 N. Ten Mile Drive
Jefferson City, MO 65109
Contact: Dan Bernskoetter
573-634-1686

Gas:
Ameren UE
Engineering Department
Jefferson City, MO
Contact: 573—681—7522


Sanitary & Storm Sewer: City of Jefferson Dept. of Community Development 320 East McCarty Street Jefferson City, MO 65101 Contact: Jim Fischer 573—634—6410

Television: Mediacom 1922 Southridge Drive Jefferson City, MO 65109 Contact: Heath Little 573—635—0245



NOTE: The Contractor will be responsible to call the Missouri One Call System 1-800-344-7483 and have the underground utilities

TE: UNDERGROUND FACILITIES, STRUCTURES AND UTILITIES, HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS, AND THEREFORE THEIR LOCATIONS MUST BE CONSIDERED APPROXIMATE ONLY. THERE MAY BE OTHERS, THE EXISTENCE OF WHICH IS PRESENTLY NOT KNOWN.




INDEX TO SHEETS:

C100 Title Sheet

C101 Overall Site Layout and General Notes

C102 Site Layout and Grading (Entrance and Buildings)
C103 Overall Grading Plan and Street Profile

C104 Site Details





SITE PLAN - Missouri River	Bluffs Condominiums		Paul Chinn and Dick Otke	1414 West Main Street	lefferson City, MO
Project:		Client:		Location:	
смРЅ ЈОВ №. 03—137					
DRN. BY BKM CKD. BY RMB					

SHEET TITLE
PROJECT
INFORMATION

FIELD BOOK:


SHEET NUMBER


C100


Michael Berendzen L. M. A. Pode Commission Dearthan L. M. Date


Potrick E. Sullivan, P.E. Dote


Director of Community Development












Expansion Joint

Contraction Joint


TYPICAL CONCRETE JOINT DETAILS




Construction Joint

C104

SIDENALK OF





Erosion Control Notes:

This Site is greater than 5 acres and therefore falls under the requirements of a Missouri DNR Lond Disturbance Permit. The Owners of the property have submitted for approval of this permit. As a result, a Stormwater Pollution Prevention Plan has been developed for this property.

- The Contractor shall install crosion control measures as shown on the drawings prior to beginning earthwork operations.
- 2. The Contractor shall maintain all silt control measures during construction
- All silt shall remain on site and surrounding streets shall be kept clear of all mud and debris.
- 4. A sedimentation barrier is to be installed as shown. The barrier shall be constructed of either: (a.) A continuous line of touching hay bales placed and to end and securely staked to prevent movement of the bales. (See detail this sheet) (b) A continuous silt fence installed as detailed on this sheet.
- Accumulated sediment shall be removed and the sedimentation barriers maintained as needed to prevent sedimentation bypass of the barrier.
- 6. Slapes are to be left in a rough condition during grading.
- Curb inlet sedimentation barriers are to be installed around inlets and weirs where sedimentation is a concern. Inlet barriers shall be either block and gravel, or secured straw bales, or silt fence.
- Erosion control measures are to remain in place until 70% ground cover has been established.
- 9. Sediment is to be removed from storm water drainage systems.
- 10. Rip rap is to be installed at areas of concentrated flow (i.e. culvert outlets).
- Contractor is responsible for installing any additional erosion control as he/she deems necessary.
- 12. The Contractor shall provide all materials, tools, equipment and labor as necessary to install and maintain adequate erosion and siltation controls required to prevent soil erosion from loaving the project site. It shall be the Contractor's sole responsibility to ensure that methods utilized are adequate and comply with requirements of the specifications and governmental agencies having jurisdiction over the work.
- 13. The Contractor shall have the responsibility for resolving complaints in the event that complaints or damage claims are filed due to damages occurring adjacent to or downstream from property by sediment resulting from erosion on the project
- 14. At completion of site grading and other related construction activities, all disturbed areas within the project site shall be seeded, sodded, or landscaped, as shown on the landscape plan.
- 15. Topsoil is to be placed in areas unsuitable for vegetative growth.
- Temporarily seed any disturbed areas which will not be brought to final grade within 30 days.

CONSTRUCTION ENTRANCE NOTES

- Stone size Use 2" stone or reclaimed or recycled equivalent
- Length as required, but not less than 50 feet.
- Thickness Not less than six (6) inches.
- 4. Width Twenty (20) foot minimum, but not less than the full width at points where ingress or egress occurs.
- 5. Filter Cloth Will be placed over the entire area prior to placing of stone.
- Surface Water All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 3:1 slopes shall be permitted.
- Maintenance The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment
 onto public rights-of-way. This may require periodic top dressing with additional stone as conditions domand and
 repair and/or cleancut of any measures used to trap addiment. All sediment spilled, dropped, washed or tracked
 onto public rights-of-way must be removed immediately.
- Washing Wheels shall be cleaned to remove sediment prior to entrance onto public rights-of-way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping
- Periodic inspection as needed maintenance shall be provided after each rain.